

- 1.) SEE ADDITIONAL REQUIREMENTS, STD No MVSI-132C.
- 2.) ALL TRENCHING AND BACKFILL SHALL BE DONE IN ACCORDANCE WITH SECTION 306, STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION, LATEST EDITION.
- 3.) ALL TEMPORARY PAVING SHALL HAVE A MINIMUM 2" OF AC ON LOCAL STREETS AND 3" ON ALL OTHERS.
- 4.) FOR EDGE OF PAVEMENT (EP) CONDITION (NO CURB AND GUTTER), REMOVE AND REPLACE FULL DEPTH PAVEMENT (AB AND AC) REMNANTS UP TO 6'.

NOT TO SCALE





10/29/201

DATE

wile

CITY ENGINEER

PUBLIC WORKS DIRECTOR /

MORENO 0F

PUBLIC WORKS DEPARTMENT - CAPITAL PROJECTS DIVISION

PARALLEL TRENCH BACKFILL AND ROADWAY REPAIR

STANDARD PLAN

MVSI-132B-3

SHEET 2 OF 6